



INBERG-MILLER ENGINEERS

Quality Solutions Through Teamwork

October 18, 2011

12897-RE

ADDENDUM NO. FOUR TO BIDDING DOCUMENTS FOR
WIND RIVER IRRIGATION REHABILITATION PROJECT
RAY CANAL AND COOLIDGE CANAL DIVERSIONS
FREMONT COUNTY, WYOMING
SEPTEMBER 29, 2011

ITEM NO. 1

Coolidge Canal, Sheet CC-4, Detail 2, change the height of the radial gate to be 5.5 feet instead of 4.5 feet.

ITEM NO. 2

Ray Canal Fish Screen, Sheet S1, Detail A, eliminate the underdrain pipe along the footing.

ITEM NO. 3

SPECIAL PROVISIONS, SECTION 10008-FISH SCREENS, PART 2, 2.02 add the following:

The fish screen frames shall be constructed from mild steel with a corrosion resistant coating.

ITEM NO. 4

SPECIAL PROVISIONS, SECTION 01041-PROJECT COORDINATION, PART 1, 1.03.A.1, add the following:

The Owner will provide two survey control points at each site, and the Contractor will be provided the northing, easting, and elevation (x, y, z) for the control points. The control points are located within 250 feet of the structures, and the control points may be located in areas where they will be obliterated by the construction.

ITEM NO. 5

Bid items for the trash racks on the fish ladders have been added to the attached bid schedule.

END OF ADDENDUM

Attachments:

Bid Schedule

Page 1 of 1

124 East Main Street
Riverton, WY 82501
307-856-8136
307-856-3851 (fax)
riverton@inberg-miller.com

1120 East "C" Street
Casper, WY 82601
307-577-0806
307-472-4402 (fax)
casper@inberg-miller.com

350 Parsley Boulevard
Cheyenne, WY 82007
307-635-6827
307-635-2713 (fax)
cheyenne@inberg-miller.com

428 Alan Road
Powell, WY 82435
307-754-7170
307-754-7088 (fax)
powell@inberg-miller.com

193 West Flaming Gorge Way
Green River, WY 82935
307-875-4394
307-875-4395 (fax)
greenriver@inberg-miller.com

WIND RIVER IRRIGATION REHABILITATION PROJECT BID SCHEDULE

Bidders may bid on any number of projects.

Bid Schedule A, Ray Canal Diversion, Fish Ladder, and Fish Screen

NO.	ITEM	UNIT	ESTIMATED QUANTITY	UNIT PRICE (\$)	TOTAL ESTIMATED PRICE (\$)
	Ray Canal Diversion				
1	Mobilization / Demobilization	Lump Sum	1		
2	Removal and Disposal of Structures	Lump Sum	1		
3	Unclassified Excavation	Lump Sum	1		
4	Reinforced Concrete	Cubic Yard	125		
5	60" Box Culvert Cast in Place	Lineal Foot	160		
6	60" Slide Gates	Each	4		
7	Radial Gate	Lump Sum	1		
8	Trash Rack	Lump Sum	1		
9	Handrail and Walkway	Lump Sum	1		
10	Dewatering	Lump Sum	1		
11	Riprap	Cubic Yard	45		
12	Dry Land Seeding	Lump Sum	1		
13	TERO Compliance	Lump Sum	1		
Subtotal for Ray Canal Diversion					
	Ray Canal Fish Ladder				
15	Mobilization / Demobilization	Lump Sum	1		
16	Unclassified Excavation	Lump Sum	1		
17	Reinforced Concrete	Cubic Yard	70		
18	Flashboard Guides	Each	8		
19	Handrail	Lineal Foot	37.5		
20	Grating - Ladder Cover	Lump Sum	1		
21	Rock Outlet	Cubic Yard	5		
22	Dewatering	Lump Sum	1		

WIND RIVER IRRIGATION REHABILITATION PROJECT BID SCHEDULE

Bidders may bid on any number of projects.

Bid Schedule A, Ray Canal Diversion, Fish Ladder and Fish Screen (continued)

NO.	ITEM	UNIT	ESTIMATED QUANTITY	UNIT PRICE (\$)	TOTAL ESTIMATED PRICE (\$)
23	Dry Land Seeding	Lump Sum	1		
24	TERO Compliance	Lump Sum	1		
25	Trash Rack	Lump Sum	1		
Subtotal for Ray Canal Fish Ladder					
Ray Canal Fish Screen					
25	Mobilization / Demobilization	Lump Sum	1		
26	Removal and Disposal of Structures	Lump Sum	1		
27	Unclassified Excavation	Lump Sum	1		
28	Reinforced Concrete	Cubic Yard	310		
29	Walkways	Lineal Foot	115		
30	Railings	Lineal Foot	250		
31	Wall Gravel Backfill	Cubic Yard	240		
32	Base Gravel/Crushed Rock	Square Foot	7000		
33	Fish Return Pipe	Lineal Foot	370		
34	Electrical Work	Lump Sum	1		
35	Screen	Each	8		
36	Crane and Hoist	Each	8		
37	Stop Log Guides	Each	18		
38	Fencing	Lineal Foot	400		
39	Dry Land Seeding	Lump Sum	1		
40	TERO Compliance	Lump Sum	1		
Subtotal for Ray Canal Fish Screen					
Total for Bid Schedule A					

WIND RIVER IRRIGATION REHABILITATION PROJECT BID SCHEDULE

Bidders may bid on any number of projects.

Bid Schedule B, Coolidge Canal Diversion and Fish Ladder

NO.	ITEM	UNIT	ESTIMATED QUANTITY	UNIT PRICE (\$)	TOTAL ESTIMATED PRICE (\$)
Coolidge Canal Diversion					
1	Mobilization / Demobilization	Lump Sum	1		
2	Removal and Disposal of Structures	Lump Sum	1		
3	Unclassified Excavation	Lump Sum	1		
4	Reinforced Concrete	Cubic Yard	175		
5	60" Box Culvert Cast in Place	Lineal Foot	132		
6	60" Slide Gates	Each	3		
7	Radial Gate	Each	1		
8	Trash Rack	Lump Sum	1		
9	Handrail and Walkway	Lump Sum	1		
10	Dewatering	Lump Sum	1		
11	Riprap	Cubic Yard	45		
12	Dry Land Seeding	Lump Sum	1		
13	TERO Compliance	Lump Sum	1		
Subtotal for Coolidge Canal Diversion					
Coolidge Canal Fish Ladder					
14	Mobilization / Demobilization	Lump Sum	1		
15	Unclassified Excavation	Lump Sum	1		
16	Reinforced Concrete	Cubic Yard	80		
17	Flashboard Guides	Each	11		
18	Handrail	Lineal Foot	56.25		
19	Grating - Ladder Cover	Lump Sum	1		
20	Rock Outlet	Cubic Yard	5		
21	Trash Rack	Lump Sum	1		

WIND RIVER IRRIGATION REHABILITATION PROJECT BID SCHEDULE

Bidders may bid on any number of projects.

Bid Schedule B, Coolidge Canal Diversion and Fish Screen (continued)

NO.	ITEM	UNIT	ESTIMATED QUANTITY	UNIT PRICE (\$)	TOTAL ESTIMATED PRICE (\$)
21	Dewatering	Lump Sum	1		
22	Dry Land Seeding	Lump Sum	1		
23	TERO Compliance	Lump Sum	1		
Subtotal for Coolidge Canal Fish Ladder					
Total for Bid Schedule B					
Total for Bid Schedule A plus Bid Schedule B (if applicable)					

Bid Schedule Options

All bidders are to mark ONE of the boxes below. If no boxes are marked, the first option is the default.

	Bidder will accept award of any combination of the bid schedules that they bid on.
	Bidder will only accept award if all of the schedules that they bid on are awarded to them as one group.
	Bidder has bid on more than one bid schedule, but bidder will only accept award of one bid schedule.