



KEY NOTES -- RE-ROOFING:

1. NEW P.T. STACKED WOOD NAILERS OVER VAPOR RETARDER SECURED TO WITHSTAND 200 LFT.LBS.
2. TAPERED EDGE STRIP AT PERIMETER PER DETAIL DRAWINGS.
3. ENCAPSULATE WALL WITH HIGH MELT ICE AND WATER DAM PROTECTION MEMBRANE AND FLUSH SEAM PRE-FINISHED METAL WALL PANELS PER DETAIL DRAWINGS.
4. SEAL VAPOR RETARDER TO ALL CURBS AND PENETRATIONS (TYP.).
5. FLASH CURB WITH CANT STRIP, BACKER FELT AND REINFORCED BASEFLASHING PER DETAIL DRAWINGS.
6. LOWER DECK WITH PORTAL IS NOT INCLUDED.
7. EXPANSION JOINTS AT DECK AND ROOF LEVEL TIED TO VAPOR RETARDER AND ROOF MEMBRANE.
8. CRICKET ON HIGH SIDE OF CURB.

DESCRIPTION OF NEW ROOF:

VAPOR RETARDER, 2 LAYERS OF RIGID INSULATION AND ONE LAYER OF COVER BD AND TWO-PLY MOD. BIT. CAP SHEET MEMBRANE WITH ACRYLIC COATING OVER A CONCRETE DECK.

LEGEND:

- VENT PIPE
- ▭ VALVE ACCESS PORT
- # KEY NOTES
- 1/5 DETAIL NUMBER
- X/5 SHEET NUMBER
- 1/5 DETAIL REFERENCE

H:\3391\AVI\ROOF PLAN.dwg Sep 18, 2012 - 9:11am Fortiene

NO.	REVISION	DATE
1	ADDENDUM NO. 1	9/18/12

PREPARED FOR:
GR/RS/SW CO. JOINT POWERS WATER BOARD
 3 TELEPHONE CANYON RD.
 GREEN RIVER, WY 82935
 307-875-4317

PROJECT:
GREEN RIVER WATER TREATMENT PLANT CLEARWELL

DRAWING TITLE:
CLEARWELL ROOF PLAN

PHONE (307) 637-6017
 1103 OLD TOWN LANE, SUITE 101
 CHEYENNE, WY 82009
 AVI@AVIPC.COM

DATE:	08-24-12
DRAWN BY:	TF
DESIGNED BY:	KB
CHECKED BY:	BP/DJ

JOB NO.: **3391**

DRAWING NO. **3** OF **13**