

ADDENDUM NO.: -1-

PROJECT: MONA ROAD BRIDGE AT BEAVER CREEK
Crook County, Wyoming

OWNER: Crook County Road & Bridge
309 Cleveland Street
P.O. Box 995
Sundance, Wyoming 82729

ENGINEER: Consolidated Engineers, Inc.
P.O. Box 1035
Gillette, Wyoming 82717-1035

DATE: August 29, 2012

The Project Manual and Drawings for the above stated Project as previously issued are hereby modified as follows:

A. PROJECT MANUAL.

1. Tab 8, Special Provisions, SP-216.a, Seeding, Fertilizer & Sodding: Broadcast seeding will be allowed in areas that would be difficult to drill. The application rate for seeding, fertilizer, and straw mulch will be as follows:

Drilled Seeding: Seed applied at 20 lbs per acre / Fertilizer at 30 lb of available nitrogen per acre / Dry Mulch at 1.5 tons per acre.

Broadcasting & Drag: Seed applied at 30 lbs per acre / Fertilizer at 30 lb of available nitrogen per acre / Hydraulic Mulch at no less than 1 ton per acre.

B. DESIGN DRAWINGS.

1. Sheet 3.0: The location of the existing culvert within the road alignment is incorrect. It is located approximately 40 to 50 feet further to the northeast from the position shown. Also, the size is eight feet (8'), not eight inches (8") as shown on the plans.
2. There is an existing two-track trail that extends to the west-northwest from the project site. Access to this trail will be left in the vicinity of 2+70 Left. This will not be an elevated approach, but rather a graveled trail (perpendicular to the roadway) on the existing side slope. This work will be incidental to the grading and reclamation.

C. GENERAL.

1. A copy of the Notes from the Pre-Bid Conference, which was held at 9:00 A.M. on August 22, 2012, were previously mailed and emailed to all planholders.

**** ALL BIDDERS SHALL ACKNOWLEDGE THE RECEIPT OF THIS ADDENDUM NO. -1-, BY NUMBER, ON THE BID FORM.**

Issued By:

CONSOLIDATED ENGINEERS, INC.

Edward S. Scott

Edward S. Scott, P.E.